


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Rooks _____ County. Sec. 26 Twp. 9S Rge. 20 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Nadel and Gussman
Lease Name Meade Well No. 1
Office Address 3232 First National Tower - Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 3 19 48
Application for plugging filed Aug. 3 19 76
Application for plugging approved Aug. 5 19 76
Plugging commenced Aug. 26 19 76
Plugging completed Aug. 26 19 76
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Lime Depth to top 3823' Bottom 3829' Total Depth of Well 3829 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle Lime	Oil	3823'	3829'	8-5/8"	133'	None
				5-1/2"	3827'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped down 8-5/8" with 50 sacks cement 3 sacks hulls followed by 200 sacks cement.
Total amount used 250 sacks. Squeeze pressure 500#.

STATE CORPORATION COMMISSION
9/7/76
SEP 07 1976
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.
Address P. O. Box 31 - Russell, Kansas 67665

STATE OF OKLAHOMA COUNTY OF TULSA ss.
M. R. Taylor (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M R Taylor
3232 First National Tower - Tulsa, Okla. 74103
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of September 19 76

My commission expires May 11, 1979
Mildred Carter
Mildred Carter Notary Public

COPY

15-163-04032-00-00

Well: Meade #1
Location: SW SW NW Section 26-9S-20W, Rooks County, Kansas
Company: Nadel and Gussman
Contractor: Virginia Drilling Company, Inc.
Commenced: February 17, 1948
Completed: March 3, 1948
Total Depth: 3829
Elevation: 2253

FORMATION	DEPTH	TOPS:
Shale-Sand	0- 40	
Sand	40- 100	Anhydrite 1743
Shale	100- 133	Arbuckle 3823
Shale-Sand	133- 257	
Shale-Shells	257- 795	
Sand	795- 915	
Shale-Sand-Shells	915-1505	CIRCULATE
Shale-Shells	1505-1743	
Anhydrite	1743-1784	@ 3610 - 1 Hr. 10 Min.
Shale-Shells	1784-2340	@ 3620 - 1 Hr.
Shale-Lime	2340-2350	@ 3705 - 1 Hr.
Sharp Sand-Lime	2350-2400	@ 3801 - 1 1/2 Hrs.
Lime-Shale	2400-2585	
Sharp Sand-Pyrite	2585-2600	
Lime-Shale	2675-2800	Set 133' of 8 5/8" csg.
Shale-Lime	2800-2870	Set 5 1/2" cas. @ 3827'3"
Shale-Shells	2870-2915	
Shale-Lime	2915-3005	
Shale-Shells	3005-3070	
Shale	3070-3113	
Lime-Shale	3113-3130	
Shale-Shells	3130-3160	
Shale-Lime	3160-3315	
Lime	3315-3340	
Shale	3340-3365	
Lime	3365-3742	
Lime-Shale	3742-3795	
Chert-Shale-Lime	3795-3821	
Shale	3821-3823	
Dolomite	3823-3829	

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and known of his own knowledge that the Meade #1, located in the SW SW NW Section 26-9S-20W, Rooks County, Kansas, was drilled to a total depth of 3829 feet.

(SIGNED) S. A. MURPHY

Subscribed and sworn to before me this 10th day of March, 1948.

(SIGNED) MURLEE HAWKINS
Notary Public

My commission expires: February 5, 1949

RECORDED
INDEXED
FEB 15 1948
NOTARY PUBLIC