

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163 - 02243 - 00 - 00

E2-SW-NE, Sec. 15, T 9 S, R 19 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Truck Well # 6

Operator: Phillips Pet. Co.
Name &
Address

County Rooks

P.O. Box 287
St. Bend, Kansas
67530

Well Total Depth 3508 feet 114.01

Conductor Pipe: Size — feet —

Surface Casing: Size 10 3/4 feet 221 w/175

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Emty License Number _____

Address Hays, Kansas 67601

Company to plug at: Hour: 10:00AM Day: 29 Month: 3 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Gene Stearns

(company name) Phillips Pet. Co. (phone) _____

were: 7" mt @ 3497 w/150 sx (1st stage) DV. @

1559" w/ 450 ske (circ to surf) C.T.P.P. @ 3460'

Perfs @ 3063 — 3348'

Ordered 280 sx 50% poz, 6% gel, 3% cc — 2000 gal —

3 sx bulls & 7" w. Plug.

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 29 Month: 3 Year: 1984

ACTUAL PLUGGING REPORT

Empd down 7" csg. → 50 sx emt w/3 bulls

→ 20 ske gel (61 bbls 9# gal mud) → Release Wiper Plug

→ 230 ske emt.

Remarks: Halliburton

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1984
4-23-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did/ did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 4-23-84

INV. NO. _____