

4-032186

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-8

API Number: 15-163-22,282-00-00

W2 W2 SE /4 SEC. 25 , 09 , 18 W
1320 feet from S section line
2310 feet from E section line

Operator license# 8925

Lease: Deveny Well # 2

Operator: Liberty Operations & Completions

County: Rooks 118.30

Address: 308 W. Mill
Plainville, Kansas 67663

Well total depth 3640 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 8 Month: November Year: 1996

Plugging proposal received from: Charlie Farr

Company: Liberty Operations & Completions Phone: _____

Were: Order 250 sxs 60/40 pozmix - 10% gel - 800# hulls.
Run tubing to spot cement.
Emergency plugging. Rig on the hole.

12-13-96
RECEIVED
DEC 13 1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: P.M. Day: 8 Month: November Year: 1996

Actual plugging report: 8 5/8" set at 208' w/150 sxs. 4 1/2" set at 3617' with 150 sxs.
PBT 3570'. Prod. Perf. 3436' - 3440'. Hole was washed down to 1950' - lost control of
hole. Decision to plug.

Ran tubing to 1950' - spotted 100 sxs cement circulated - pulled tubing. Squeezed 4
1/2" with total 180 sxs cement with 800# hulls mixed into Max. P.S.I. 1000#. S.I.P. 700#.
Squeezed 8 5/8" with 25 sxs cement to Max. P.S.I. 500#. Held. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES 1450 NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did [] / did not [X] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE DEC 13 1996
INV. NO. 47178