

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03020-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 35-9S-22W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: COLLISON Well #: 4
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3830	0	100 SX
SURF	8.625	253	0	150 SX

\$ 124.48

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2007 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perf at 1850' and 1125'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2007 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 2061' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1157' - pumped 95 sxs cement with 200# hulls - circulated cement.
Pulled out - tied on top - pumped 140 sxs cement with 200# hulls. S.I.P. 50#.
Tied on backside with 10 sxs. S.I.P. 400#.
Tied back on to the 5 1/2" - squeezed with 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3733	3738		
3662	3666		

INVOICED

DATE 4-12-07
INV. NO. 2007061580

Remarks: SWIFT SERVICES, INC.-TICKET #11474.

Plugged through: TBG

District: 04

AD

Signed

Marvin Mills

(TECHNICIAN)

APR 04 2007

RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

APR 09 2007

CONSERVATION DIVISION
WICHITA, KS

PT

SASNAK DEVELOP. INC

#4 COLLISON

35-9-22W
NW SW SW

Contr. K & E DRILG CO

GRAHAM County

E 2357^{RR} Comm. 8-21-58

Comp. 10-24-58 IP

98 BOPD

PHY POT

Tops	Depth	Datum
Anh	1813-	+526
HEEB	3533	-1176
TOR	3575	-1218
LANS	3589	-1232
B/KC	3820	-1463
ID	3830	-1473

Casing
8" 253
5" 3830
DST 3720-50/1 1/2 HR, 120' G,
180' V HO & GCM, BHP 220#
DST 3748-85/1 HR, 15' M, BHP
325#
PERF 3662-66, NS: ACID 1500
PLUG 3752: PERF 3733-38:
ACID 1500: SWB 34 80/9 HR:
BRASSFIELD POOL PLUG 3830

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS