

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20592-00-00
Spot: NWNENW Sec/Twnshp/Rge: 10-19S-31W
330 feet from N Section Line, 1840 feet from W Section Line
Lease Name: SCHMIDT TRUST Well #: 10-1
County: SCOTT Total Vertical Depth: 4400 feet

Operator License No.: 33802
Op Name: SUNSTONE OPERATING COMPANY, LL
Address: 101 N. ROBINSON, SUITE 810
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1696		CMT CIRCULATED
PROD	7.625	4393		WITH 720 SX CMT
SURF	10.75	330		WITH 270 SX CMT

\$ 143.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/19/2007 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: BILLIE GRIGGS Company: SUNSTONE ENERGY Phone: (405) 601-1538

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING METHOD

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2007 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT & 400# HULLS AT 4383'. 1ST PLUG AT 2198' WITH 50 SX CMT. NO CIRCULATION. PULL TUBING TO 1698'. 2ND PLUG AT 1698' WITH 75 SX CMT. 3RD PLUG AT 1007' WITH 50 SX CMT. 4TH PLUG AT 350' WITH 50 SX CMT. 5TH PLUG AT 69' WITH 15 SX CMT. FULL CIRCULATION ON ALL PLUGS. PUMP 3 SX CMT DOWN 7 5/8" X 10 3/4" ANNULUS. PRESSURE TO 1000#.

Perfs:


Top	Bot	Thru	Comments
4393	4665	OH	

INVOICED
DATE 4-10-07
INV. NO. 2007061571

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

CONSERVATION DIVISION

Plot