

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23007-00-00  
Spot: CSESWNE Sec/Twnshp/Rge: 15-9S-19W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: NOVOTNY B Well Number: 1-15  
County: ROOKS Total Vertical Depth: 3503 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY  
Address: 805 CODELL RD.  
CODELL, KS 67663

Conductor Pipe: Size feet: 8 1/3.85  
Surface Casing: Size 8.625 feet: 227 135 SX CMT  
Production: Size 5.5 feet: 3500 250 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/08/2002 9:00 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY  
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-7202

Proposed Plugging Method: Perf at 1500' and 850'. WLM 3450'.  
Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/08/2002 12:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 5 1/2" casing with 25 sxs cement with 300# hulls in cement, followed with 25 sxs gel, followed with 125 sxs cement.  
Max. P.S.I. 800#.  
Squeezed 8 5/8" casing with 25 sxs cement plus 100# hulls in cement.  
Max. P.S.I. 500#.

RECEIVED  
JUN 26 2002  
6-26-02  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed

Dennis F. Hamel  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-27-02

NOV. 2002 2002062014

JUN 18 2002

replacement card

LANSING ENERGY CORPORATION  
WICHITA, KS 67202

15-09 -19W  
SE SW NE

#1-15 NOVOTNY "B"

site: 2 N & 6 W OF PLAINVILLE, KS	city: ROOKS	API 15-163-23007
contr: R & C DRILLING, INC	field: JELINEK	
geol: RICHARD L. CORNETT		
fr date 07/06/88	spd date 07/18/88	drlg comp 07/26/88
	card issued 09/28/88	last revised 01/25/89


ELV: 2075 KB LOG
tops.....depth/datum
HEEB.....3214 -1139
TOR.....3236 -1161
LANS.....3256 -1181
BKC.....3462 -1387
ARB.....3498 -1423
RTD.....3503 -1428

IP status:  
OIL, P 10 BO & 350 BWPD, ARB 3500-3503,  
INFO RELEASED: 1/25/89 - WAS OIL WELL - TIGHT HOLE  
CSG: 8-5/8" 227 / 135 SX, 5-1/2" 3500 / 400 SX  
NO CORES  
DST (1) 3299-3361 (LKC), / 30-60-30-60, REC 365' MDY  
GSY SW, W / TR OIL, 365' GSY SW ISIP 829# FSIP  
722# IFP 106# -243# FFP 295# -347# IHP 1652# FHP  
1632#  
DST (2) 3369-3420 (LKC), / 30-60-30-60, REC 450' MDY  
GSY SW ISIP 778# FSIP 737# IFP 64# -127# FFP  
190# -222# IHP 1682# FHP 1612#

COPYRIGHT 1989  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

LANSING ENERGY CORPORATION  
WICHITA, KS 67202

15-09 -19W  
SE SW NE

#1-15 NOVOTNY "B"

DST (3) 3422-3463 (LKC), / 30-30-30-30, REC 5' M ISIP 471# FSIP 74# IFP 42# -42# FFP  
42# -42# IHP 1732# FHP 1662#  
MICT - CO, (ARB OH), AC 300 GAL (MCA), SO, SET 2-7/8" TBG AT 3477, NO PKR, POP, P 10 BO  
& 350 BWPD, 11/30/88