

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00507-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 25-3S-24W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FOUGHT Well #: 3
County: NORTON Total Vertical Depth: 3778 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3771	0	150 SX
SURF	8.625	260	0	135 SX

\$122.79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2007 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 375 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 500'. Bad casing leak at 1530'.
Casing collapsed 1530' - unable to clean out - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2007 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 2500'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1250'. Allied pumped 85 sxs cement with 300# hulls - circulated cement.
PTOH. Squeezed 5 1/2" casing with 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Hooked up to backside and pumped 50 sxs.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3771	3778	OH	

INVOICED
DATE 4-12-07
INV. NO. 2007061583

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
FORM CP-2/3

APR 09 2007

CONSERVATION DIVISION
WICHITA, KS

APR 06 2007

Handwritten initials

WOOD RIVER OIL & REFG

#3

FOUGHT

25-3-24W

APP SW SW SE

Contr. EMPIRE DRILLING

NORTON

County

E 2457RB Comm. 2/5/54

Comp. 3/19/54

IP 169 BOPD

Tops	Depth	Datum
HEEB	3477	-1020
LANS	3517	-1060
ARB	3767	-1310
T D	3778	-1321


Casing

8"256

SWB 8 BOPH, NATL

5"3769

NORTON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS