

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14789-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 32-20S-11W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHEUFLER Well #: 3
County: BARTON Total Vertical Depth: 3367 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3866	0	100 SX
SURF	8.625	567	0	325 SX

\$109.43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2007 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 700# hulls.
Casing leaks - high fluid level.
Perfs - no records.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2007 4:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2000'. Rigged to tubing and pumped 200 sxs 60/40 pozmix with 700# hulls mixed in.
Cement circulated out of 8 5/8" casing and 5 1/2" casing.
Shut in 8 5/8" casing and pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 100 sxs 60/40 pozmix.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

INVOICED
DATE 4-12-07
INV. NO. 2007061584

Remarks: QUALITY CEMENTING & ACID SERVICES-TICKET #1399.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 04 2007

APR 09 2007

CONSERVATION DIVISION
WICHITA, KS

PEP

32-20-11W
NW NW NW

BAY PETROLEUM CORPORATION #3 SCHEUFLER


Contr. PICKRELL DRILLING COMPANY BARTON County

E 1813 Comm Comp. 7-11-52 IP 116 BOPD
PHY POT

Tops	Depth	Datum
HEEB	2978	-1165
BR LM	3109	-1296
LANS	3123	-1310
ARB	3362	-1549
T D	3367	-1554

Casing
 8" 567 DP: 20 GOPH: DD
 5" 3363 3367: 1/2 BOPH: ACID
 500: 15 BOPH

KOWALSKY POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS