

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05201-00-00
Spot: NENESE Sec/Twnshp/Rge: 24-11S-18W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: MARSHALL E Well #: 3
County: ELLIS Total Vertical Depth: 3454 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	3292	0	w/200 sxs cmt
PROD	5.5	3454	0	w/125 sxs cmt
SURF	8.625	1118	0	w/375 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2007 12:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: TOM BERENS Company: LARIO OIL & GAS COMPANY Phone: (785) 625-4423

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2007 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 155 sxs cement with 500# hulls.
Max. P.S.I. 1200#. S.I.P. 200#.
Hooked up to the 4 1/2" & 5 1/2" annulus - instant pressure.
Hooked up to the 8 5/8" annulus - mixed and pumped 145 sxs cement.
S.I.P. 200#.

Perfs:

INVOICED
DATE 4-12-07
INV. NO. 2007061587

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 09 2007

CONSERVATION DIVISION
WICHITA, KS

APR 05 2007

PET

24-11-18W

LARIO OIL & GAS CO #3 MARSHALL 'E' NE NE SE

Contr. _____ ELLIS County

E 1876 Comm. 12-22-46 Comp. 1-8-47 IP 313 BOPD

Tops	Depth	Datum	Casing
ANH	1110		8" 1122
			5" 3456
LANS	3087		Perf 78/3406-19: A/500
			Swb 9 BOPH/6 hrs
ARB	3406		
TD	3456		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

