

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21179-00-00  
Spot: SWNE Sec/Twnshp/Rge: 1-33S-30W  
1980 feet from N Section Line, 2125 feet from E Section Line  
Lease Name: EDNA COLLINGWOOD Well #: 7  
County: MEADE Total Vertical Depth: 5900 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY STE. 350  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	1000		WITH 625 SX CMT

\$191.75

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/03/2007 3:00 PM  
Plug Co. License No.: 33784 Plug Co. Name: TRINIDAD DRILLING LIMITED PARTNERSHIP  
Proposal Rcvd. from: RON Company: PETROSANTANDER Phone: (620) 272-7349

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 75 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE  
Date/Time Plugging Completed: 04/03/2007 5:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

Perfs:


12 1/4" HOLE DRILLED TO 1500'. SET 9 5/8" @ 1035'. CMT CIRCULATED. 1ST PLUG AT 1560' WITH 75 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED  
DATE 4-12-07  
INV. NO. 2007061589

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed Jerry W. Stapleton PIRT JT  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-113

APR 09 2007

CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten signature]*