

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20338-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 13-28S-21W  
2310 feet from N Section Line, 330 feet from W Section Line  
Lease Name: BRENSING Well #: 2  
County: FORD Total Vertical Depth: 5175 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5172	2400	WITH 150 SX CMT
SURF	8.625	629		WITH 400 SX CMT

\$ 168.19

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2007 12:00 PM  
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC  
Proposal Rcvd. from: BRIAN SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 672-5713

Proposed Plugging Method: SAND TO 5020' & 4 SX CMT. PLUG AT 1380' WITH 200# HULLS - 15 SX GEL - 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/02/2007 7:32 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 5020' WITH 4 SX CMT. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1380' WITH 200# HULLS - 15 SX GEL - 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
5120	5122		
5071	5074		

INVOICED  
DATE 4-12-07  
INV. NO. 2007061593

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR.

Plugged through: CSG

District: 01



Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 09 2007

CONSERVATION DIVISION  
WICHITA, KS

Form CR-2