

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14401-00-00
Spot: SWSE Sec/Twnshp/Rge: 9-20S-11W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SCHEUFLER Well #: 1
County: BARTON Total Vertical Depth: 3334 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD, SUITE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	5.5	501	501	Packer remained
PROD	8.625	3300	0	w/100 sxs cmt
SURF	13	167	0	w/100 sxs cmt

\$ 108.36

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2007 12:00 PM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC
Proposal Rcvd. from: RICK POPP Company: T-N-T ENGINEERING, INC. Phone: (620) 653-2713

Proposed 04/02/2007 - Ordered 100 sxs 60/40 pozmix - 10% gel with 3% cc.
Plugging 04/03/2007 - Ordered 325 sxs 60/40 pozmix - 10% gel - 800# hulls - 42 sxs gel.
Method: Packer stuck in the hole at 501'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2007 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

04/02/2007
Plains, Inc. ran in hole with tubing to 3300'.
Quality Cementing rigged to tubing and pumped 100 sxs 60/40 pozmix - 10% gel with 3% c.c. and 400# hulls mixed in.
Perf Tech perfed at 1350' and 495' - two shot perf.
04/03/2007
Plains, Inc. ran in hole and tagged cement at 2824'.
Quality Cementing rigged to tubing and pumped 38 sxs gel.
Plains, Inc. pulled tubing to 1350'.
Quality Cementing rigged to tubing and pumped 260 sxs 60/40 pozmix with 400# hulls mixed in to circulate cement into pit area.
Pulled tubing - rigged to backside of 13" casing and pumped 50 sxs.
Max. P.S.I. 300#. S.I.P. 100#.
Topped off 8 5/8" casing with 10 sxs - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3300	3334		Arbuckle

INVOICED
DATE 4-12-07
INV. NO. 2007061594

Remarks: QUALITY CEMENTING & ACID SERVICES-TICKET #1397.

Plugged through: TBG

District: 04

10

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

APR 09 2007

CONSERVATION DIVISION
WICHITA, KS

APR 04 2007

[Signature]