

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21236-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 22-25S-9W  
4950 feet from S Section Line, 4385 feet from E Section Line  
Lease Name: HARRIS Well #: 1-22  
County: RENO Total Vertical Depth: 4005 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3995		150 SX
SURF	8.625	208		190 SX

\$ 130.16

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2007 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand back to 3800' cap w/ 5 ks cement, 35 sks @ 1300', 35 sks @ 750', @ 260' cir cmt. to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/15/2007 3:00 PM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

SAND BACK TO 3800' CAPPED WITH 5 SKS CEMENT; PULLED CASING FROM 2600' TO 1300' FOR BOTTOM SALT PLUG 35 SKS CEMENT; PULLED BACK TO 750' PUMP 35 SKS CEMENT; PULLED CASING TO 290' CIR. CEMENT TO SURFACE -80 SKS, PULLED CASING OUT OF HOLE.

Perfs:

Top	Bot	Thru	Comments
3856	3860		

INVOICED  
DATE 4-16-07  
INV. NO. 2007061611

Remarks: TOP PULL FELL BACK TO 90' WITH 20' FLUID. PLACE 1" IN HOLE AND PUMPED 50 SKS OF CEMENT TO SURFACE. COPELAND TICKET #CO31668

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

*[Signature]*

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

APR 10 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

*[Signature]*

*[Signature]*