

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21387-00-00
Spot: N2SENE Sec/Twnshp/Rge: 10-25S-9W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: DILLON Well #: 4-10
County: RENO Total Vertical Depth: 4000 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3995		150 SX
SURF	8.625	227		190 SX

\$ 130.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2007 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3820' 5 SKS CMT. , 35 SKS @ 1350', 35 SKS @ 750', 280' CIR, CMT TO SURFACE. PBTD 3941-PERFS 3868-78, 3881-85

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/13/2007 4:00 PM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

SAND BACK TO 3800' CAP WITH 5 SKS OF CEMENT. PULLED CASING FROM 2330' SET BOTTOM SALT PLUG 35 SKS. @ 1350'. PULLED CASING TO 750' PLACED 35 SKS OF CEMENT, PULLED TO 280' CIRCULATED CEMENT TO SURFACE 75 SKS.

Perfs:

Top	Bot	Thru	Comments
3881	3885		
3868	3878		

INVOICED
DATE 4-16-07
INV. NO. 2007061611

Remarks: COPELAND TICKET# C031668 TOP PLUG FELL BACK 140' WITH 30' FLUID. PLACED 1" IN AND PUMPED ANOTHER 45 SKS OF CEMENT TO TOP OF HOLE.

Plugged through:

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

