

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-03021-00-01
Spot: E2W2NW Sec/Twnshp/Rge: 19-24S-4W
4016 feet from S Section Line, 4407 feet from E Section Line
Lease Name: MUELLER A Well #: 1
County: RENO Total Vertical Depth: 3387 feet

Operator License No.: 33324
Op Name: ALLAM PRODUCTION, INC.
Address: PO BOX 2325
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3337		
SURF	10.75	442		

\$ 110.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2007 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3,335' and top with 10 sacks of cement. Run tubing to 650' and spot 30 sacks of cement. Pull tubing to 450' and spot 30 sacks of cement. Pull tuing to 250' and circulate cement to the surface.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 01/05/2007 3:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

1/5/2007 -- Ran tubing to 3317' and spotted 40 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 651' and circulated 160 sacks of cement to the surface.
1/8/2007 -- Operator checked cement and cement was down 103'. Operator topped cement off with 1-1/2 yds of cement. Cement at surface.
60/40 posmix with 4% gel
Copeland #C03140
Slurry mix by Hutchinson Concrete

Perfs:

RECEIVED
KCC DISTRICT #2
JAN 23 2007
WICHITA, KS

INVOICED
DATE 4-16-07
INV. NO. 2007061602

Remarks:
Plugged through: TBG

District: 02

Signed Michael B. Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

M

PT