

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03017-00-00
Spot: SESESW Sec/Twnshp/Rge: 35-9S-22W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: COLLISON Well #: 1
County: GRAHAM Total Vertical Depth: 3785 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3785	0	85 SX
SURF	8.625	251	0	150 SX

\$ 123.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/06/2007 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 360 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/06/2007 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto tubing - pumped 130 sxs cement.
Max. P.S.I. 1100#. S.I.P. 1100#.
Tied onto the 5 1/2" - pumped 110 sxs with 300# hulls.
Max. P.S.I. 800#. S.I.P. 800#/
Cement circulated out the 8 5/8".

Perfs:

Top	Bot	Thru	Comments
3709	3715		

INVOICED
DATE 4-16-07
INV. NO. 2007061603

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

APR 10 2007
CONSERVATION DIVISION
WICHITA, KS

APR 09 2007

Handwritten initials

SASNAK DEVELOPMENT

#1 COLLISON

35-9-22W

SE SE SW

Contr. K & E DRLG

GRAHAM

County

E. 2332RB Comm.

Comp. 2-1-57

IP 25 BOPD

Tops	Depth	Datum
HEEB	3525	-1193
TOR	3548	-1216
LANS	3563	-1231
TD	3785	-1453

Casing

8" 251

5" 3785

DST 3693-3726/1 HR, 80' V SL

OCM, 30' O & GCM, 90' HO &

GCM, BHP 915#


DST 3732-85/1 HR, 120' OILY

MUD, BHP 1020#

PERF 24/3709-15: 3717-21

BRASSFIELD

ACID 2500



INDEPENDENT OIL & GAS SERVICE

WICHITA, KANSAS