

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00411-00-00
Spot: E2NWSW Sec/Twnshp/Rge: 28-21S-3W
1986 feet from S Section Line, 4546 feet from E Section Line
Lease Name: DAVID H. SCHROEDER Well #: 1
County: MCPHERSON Total Vertical Depth: 3125 feet

Operator License No.: 32778
Op Name: CAT ENERGY, LLC
Address: PO BOX 507
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3118	1680	
SURF	8.625	225		

\$ 101.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2007 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DUANE PURSER Company: CAT ENERGY, LLC Phone: (620) 245-9091

Proposed Plugging Method: Sand to 3,050' & top with 5 sxs. cement. Rip 5 1/2" casing. Pull casng to 500' & spot 35 sxs. cement. Pull casing to 275' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/05/2007 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report: _____ Perfs: _____

Sanded to 3,050' & topped with 5 sxs. cement. Ripped casing at 1,680'. Pulled casing to 502' & spotted 35 sxs. cement. Pulled casing to 270' & circulated 150 sxs. cement to the surface, Checked top plug on 2/28/2007 & cement was down 90'. On 3/5/2007 ran 1" tubing to 90' & circulated 30 sxs. cement to the surface.

INVOICED
DATE 4-16-07
INV. NO. 2007061606

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND. INVOICE#31518 & #31661.

Plugged through: CSG

District: 02

Signed Michael P. Wilson
(TECHNICIAN)

M

RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2007
CONSERVATION DIVISION
WICHITA, KS

PKT