

15-163-02469-00-01

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, KansasDEC 13 1966  
12-13-66  
CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Robinowitz Oil CompanyComplete Address: 1322 E. 50th St. Tulsa, OklahomaLease Name Rempe Well No. 1Location NW SE SE Sec. 21 Twp. 9 Rge. 18 (E) (W) XCounty Rooks Total Depth 425'Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       Other well as hereafter indicated: Reopened and washed down to 425'Plugging Contractor: Co. Tools Sun cementing Co.Address: Hays, Kansas License No.       Operation Completed: Hour 3:30 P Day 8 Month 12 Year 1966

## The Above well was plugged as follows:

8 5/8 csg set at 185' cwc. 5 1/2 csg set at approx. 3500'1948 --- 425' of 5 1/2 csg recov. Abandoned and plugged.1966--- Cleanout to 425' Couldn't get inside 5 1/2 csg.Pumped 40 sc gel down 8 5/8 csg.Run 2" tubing to 400' and displaced 40 sc cement.Mud to 185' and displaced 45 sc cement.Mud to 40' and circ. 15 sc cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. Massey  
Well Plugging SupervisorDATE 12/13/66INV. NO. 4439-W