

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21,756 ✓ R

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Southern States Oil Co.

Complete Address P.O. Box 1365, Great Bend, Ks. 67530

Lease Name A. Stahl Well No. 6

Location NE SW NW Sec. 21 Twp. 9 Rge. 18 (East) (West) (West)

County Rooks Total Depth 3651'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co.

Address 1720 K.S.B. Bldg., Wichita, Ks 67202 License No. _____

Operation Completed: Hour: 9:30 PM Day: 17 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 256' S.P. cnc. w/ 165 sacks common - 2% Gel. - 3% Cal. Cl.

Ordered 140 sacks 50% po mix - 4% Gel. - 3% Cal. Cl. + 8 5/8" plug.

Spot w/ drill stem w/ heavy mud between all plugs.

1st plug C 850' w/ 80 sacks.

2nd plug C 280' w/ 40 sacks.

3rd plug - solid bridge of shells + plug C 40' w/ 10 sacks.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 256' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Stahl
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1982
8-24-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED
DATE 9-8-82
INV. NO. 1054-W