

15-163-20001-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1967  
1-23-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Robinowitz Oil Company

Complete Address: 1322 East 50th Street Tulsa, Oklahoma

Lease Name Rempe Well No. 5

Location SW NE SE Sec. 21 Twp. 9 Rge. 18 (E) (W) X

County Rooks Total Depth 3580'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: B-B Drilling Inc.,

Address: Wichita, Kansas License No. 598

Operation Completed: Hour 7 P Day 20 Month 1 Year 1966

The Above well was plugged as follows:

RTD 3580' 8 5/8 csg set at 201' cwc.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 25 sc cem.  
thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sc cem. thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lawrence Messing  
Well Plugging Supervisor

DATE 1/23/67  
INV. NO. 4645-u