

15-163-01570-00-00

Form CP-3
Rev. 6-26-62

JK
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1965
6-14-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Robin Oil Co
Complete Address: 1322 E 50th Tulsa, Okla
Lease Name Widman Well No. 4
Location NW SW SW Sec. 21 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3583
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractors: Knight Casing Pulling Co
Address: Chase, Kans License No. 436
Operation Completed: Hour 5PM Day 7 Month 6 Year 65

The Above well was plugged as follows:

8 5/8" 181' circulated with cement - 5 1/2" 3580' with 75 sax cement
packer lost in hole at 3100', sand back to 3040' set 4 sax cement with
dump bailer - pulled 900' 5 1/2" to 600' pumped hole full heavy mud- hole
pressured up, did not circulate pulled pipe to 400' circulated hole with
mud through 5 1/2" (4b sax Gel) spotted 20 sax cement through 5 1/2" at 400',
heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud
to 35', cement 35' to 0'.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 6/14/65
INV. NO. 1310-W

Signed: [Signature]
Well Plugging Supervisor