


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1973
3-29-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.
Complete Address Box 352 Russell, Kansas 67665
Lease Name Stahl Well No. 1
Location SW NW NW Sec. 21 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3590'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by Allied Cementing Co.
Address License No.
Operation Completed: Hour 12:30 P Day 28 Month 3 Year 1973

The above well was plugged as follows:

Total Depth 3590' 8 5/8 csg set at 165' cwc.
5 1/2 csg set at 3583' cw 150 sk cem.
5 1/2 csg squeezed at 968'. No pipe recovered.
Pumped down 5 1/2 csg with 20 sk cem - 35 sk gel & water W/400 lbs hulls -released
5 1/2 plug and pumped 60 sk cem W/100 lbs hulls. 1300 lbs PP 500 lbs SIP
Pumped down annulus (5 1/2-8 5/8) with 40 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eric L. Massey
Well Plugging Supervisor

DATE 3/29/73
INV. NO. 9188-W