

R KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1963

6-14-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Phillips Pet Co

Complete Address: Box 287 Great Bend, Kansas

Lease Name Landry Well No. 4

Location SE NW NW Sec. 14 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3483

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kans License No. 49

Operation Completed: Hour 2PM Day 12 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" 1490' with 775 sax cement - 5 1/2" 3478' with 200 sax cement -
PB to 3200' - Perf 3145'.

Filled with sand to 3120', set 4 sax cement with dump bailer - pulled
2505' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at
550' (20 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy
mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to
35', set bridge and filled to 0' with cement.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6/14/63

INV. NO. 7264-W