

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1962  
1-30-62  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks  
Location: SW NW NE Sec. 14 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 19  
Name of Field: \_\_\_\_\_ Total Depth: 3473

I have this date completed supervision of plugging of:

Lease Name: Ruder Well No. 3

Operator's Full Name: Theodore Gore

Complete Address: 650 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor Arnett Casing Pulling & Globe Cementing Co

Address: Hoisington, Kansas License No. 265

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No  \_\_\_\_\_

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 24 Month 1 Year 62

The above well was plugged as follows:

8 5/8" 164' circulated with cement - 5 1/2" 3472 with 150 sax cement  
PB 3430' - perforated 3210',

Plugs and sand to 3190' - set 4 sax cement with dump bailer - pulled  
2800' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" ( 25 sax Ge  
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 160', displaced  
20 sax cement through 5 1/2" at 160', heavy mud to 35', set bridge and  
10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: Leson Leary  
Conservation Division Agent

Reviewed: Harold Morris  
Field Supervisor

Remarks:

INVOICED  
DATE 2/2/62  
INV. NO. 4424-W