

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

OCT 24 1962
10-24-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name I. O. Miller
Complete Address: 619 Brown Bldg Wichita, Kansas
Lease Name Allphin Well No. 1-B
Location SE NW NW Sec. 32 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3739
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: C & G Drg Co
Address: Wichita, Kansas License No.
Operation Completed: Hour 9:15PM Day 20 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 177' circulated with cement.
Circulated hole with heavy mud, set cementing plug at 550', displaced
20 sax cement through drill pipe at 550', heavy mud to 170', set plug
and 20 sax cement, heavy mud to 40', set plug, 1/2 sack hulls and filled
to bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/29/62
INV. NO. 5908-W

Signed: [Signature]
Well Plugging Supervisor