

KANSAS

FORM CP-3  
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163 - 21,496 - 00-00 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Lebsack Oil Production, Inc.

Complete Address P.O. Box 489 Hays, Ks. 67601

Lease Name Allphn Well-No. 1

Location SE NE NE Sec. 32 Twp. 9 Rge. 19 (East) (West)

County Rooks Total Depth 3780'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Ranger Drilling Inc.

Address P.O. Box 856 Hays, Ks. 67601 License No. \_\_\_\_\_

Operation Completed: Hour: 11:00 AM Day: 8 Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All  Part  None XXX

The above well was plugged as follows:

8 5/8" 265' S.P. cuc. W/ 150 sacks common 2% Gel- 3% CA1.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel- 3% CA1.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 1020' W/ 70 sacks cement

2nd plug @ 260' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
1-11-82

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

28-82  
9287-W