

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25618-00-00
Spot: SENESE Sec/Twnshp/Rge: 10-13S-17W
1725 feet from S Section Line, 330 feet from E Section Line
Lease Name: CATHERINE UNIT Well #: 3-7 TWIN
County: ELLIS Total Vertical Depth: 1541 feet

Operator License No.: 7064
Op Name: DORZWEILER, LEO R. DBA CATTLEM
Address: 2260 CATHERINE RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	223		

\$ 50.08

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 03/12/2007 8:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: CATTLEMANS OIL OPERATIONS Phone: (785) 625-5394

Proposed	Ordered 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Plugging	Space all plugs with heavy drilling mud through drill pipe.
Method:	Note: Top joint of surface pipe is 8 5/8" and was swedged to 10 3/4" to depth of 223'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2007 10:30 AM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Hole was lost in the Salt Section.
25 sxs were put in Anhydrite at 1225' - 100 sxs at 725'.
Both plugs were lost down hole.
Drilling rig was moved off location.
Pulling unit used to finish plugging - TOC 1416'.
Ran tubing to 1225' w/25 sxs.
Pulled tubing to 725' - pumped 75 sxs cement.
Pulled tubing to 265' - pumped 40 sxs cement - water and mud circulated.
Pulled tubing to surface.
Used one joint to plug rathole with 15 sxs and mousehole with 10 sxs.
Placed one joint in 10 3/4" surface pipe and circulated cement with 10 sxs.

Perfs:

INVOICED
DATE 3-20-07
INV. NO. 2007061484

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 04

MA

Signed Bruce D. Basye
(TECHNICIAN)

MAR 13 2007

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

MAR 16 2007

CONSERVATION DIVISION
WICHITA, KS

RET