

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-19100-00-00  
Spot: NESESW Sec/Twnshp/Rge: 9-21S-11W  
929 feet from S Section Line, 2960 feet from E Section Line  
Lease Name: MANNING B Well #: 3  
County: STAFFORD Total Vertical Depth: 3459 feet

Operator License No.: 3208  
Op Name: K & N PETROLEUM, INC.  
Address: 513 W. 6TH ST  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3459	0	WITH 75 SX CMT
SURF	8.625	271		WITH 225 SX CMT

\$ 112.42

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2007 1:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NIMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: SAND TO 3320' & 4 SX CMT WITH BAILER OR SET CIBP @ 3320' & 4 SX CMT OR PUMP 25 SX CMT TO BOTTOM. 1ST PLUG SPOT THROUGH CASING PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2007 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TUBING TO 3320' & PUMPED 25 SX CMT. PULLED TUBING TO 600'. PUMPED 75 SX CMT CIRCULATING CMT TO SURFACE. PULLED TUBING OUT OF HOLE. TOPPED OFF 4 1/2" WITH 35 SX CMT. PUMPED 100 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 300 PSI. SHUT IN PRESSURE 200 PSI.

Perfs:

Top	Bot	Thru	Comments
3425	3427		
3370	3373		

INVOICED


DATE 3-20-07

INV. NO. 2007061489

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: TBG

District: 01



Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 15 2007  
CONSERVATION DIVISION  
WICHITA, KS

PLG