

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21841-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 28-20S-13W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LINDHOLM Well #: 1
County: BARTON Total Vertical Depth: 3443 feet

Operator License No.: 33153
Op Name: KRIER, ROGER DBA KRIER OIL OPERA
Address: P. O. BOX 763
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3442	0	100 SX
SURF	8.625	250	0	225 SX

\$ 111.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2007 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 793-0832

Proposed Plugging Method: Ordered 750 sxs 6040 pozmix - 10% gel - 1400# hulls.
Casing leaks - high fluid level.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2007 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

03/12/2007
RIH with tubing to 2000'. Rigged to tubing - pumped 100 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 1844'. Rigged to tubing - pumped 135 sxs 60/40 pozmix - tubing stuck in the hole - left set two hours.
Pulled tubing to 1625'. Tubing stuck. Rigged to tubing - pumped 200 sxs 60/40 pozmix with 200# hulls mixed in - left set two hours.
Rigged back on tubing - pumped 215 sxs cement with 600# hulls mixed in.
Left 42 joints tubing with small mill on tubing in the hole.
03/13/2007
RIH with tubing to 280'. Rigged to tubing - pumped 75 sxs cement with 300# hulls mixed in to circulate cement out 4 1/2" casing and 8 5/8" casing.
Shut in 8 5/8" casing - rigged to 4 1/2" casing with a swedge and pumped 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3407	3411		


INVOICED
DATE 3-20-07
INV. NO. 2007061490

Remarks: ALLIED CEMENTING COMPANY-TICKET #30588.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

MAR 16 2007

CONSERVATION DIVISION
WICHITA, KS

MAR 13 2007

PKT

WOODMAN & IANNITTI DRILLING CO.
 1008 DOUGLAS BLDG.

WICHITA, KS. 67202


#1 LINDHOLM

28-20-13W
 SW NW NW

CONTR WOODMAN & IANNITTI DRLG. CTY BARTON

GEOL _____ FIELD SANDROCK

E 1889 KB CM 2/4/80 CARD ISSUED 5/9/80 IF P 20 BOPD
 LANS 3407-3411



API 15-009-21,841

SMP	TOPS	DEPTH	DATUM
ANH		756	+1133
HEEB		3147	-1258
LANS		3277	-1388
RTD		3443	-1554

8-5/8" 250/225sx, 4 1/2" 3442/100sx
 DST (1) 3397-3417/30-30-30-30, REC 1600'
 G, 45' HO&GCM, 120' MDY GSY 0,
 SIP 787-763#, FP 47-59/78-82#
 MICT - CO, PF 12/3407-3411, AC 2500,
 SWB 18 BOPH/2 HRS, POP, P 20 BOPD &
 TR WTR

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS