

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-23646-00-01

Spot: NWNENWNW

Sec/Twnshp/Rge: 27-33S-8E

5036 feet from S Section Line, 4340 feet from E Section Line

Lease Name: COFFMAN

Well #: 2

County: CHAUTAUQUA

Total Vertical Depth: 2280 feet

Operator License No.: 32557

Op Name: BLUESTEM, INC

Address: 1226 W COUNTY LINE RD
CEDAR VALE, KS 67024

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR	2.375	2015	2015	PULLED PACKER

PROD	5.5	2272	0	
------	-----	------	---	--

SURF	8.625	150	0	100 SX
------	-------	-----	---	--------

T1	2.375	2015	2015	
----	-------	------	------	--

\$ 74.10

Well Type: EOR

UIC Docket No: E22504.2

Date/Time to Plug: 01/05/2007 8:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE

Company: ELMORES, INC.

Phone: (620) 249-2519

Proposed Plugging Method: TO RUN 1" WORK-STRING INSIDE 4.5" CASING & PUMP GEL & CEMENT FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE

WitnessType: NONE

Date/Time Plugging Completed: 01/05/2007 5:00 PM

KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" WORK-STRING INSIDE 5.5" CASING TO 2250', GELLED HOLE & PUMPED 15 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 500' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 75 SACKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2214	2220		
2062	2068		

RECEIVED
KCC DISTRICT #3

FEB 27 2007

CHANUTE, KS

RR

INVOICED

DATE 3-16-07

INV. NO. 2007061480

Remarks: PLUGGED INJECTION WELL.

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

RECEIVED

MAR 14 2007 CP-2/3

KCC WICHITA