

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20202-00-00  
Spot: NENENW Sec/Twnshp/Rge: 35-9S-23W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RICE Well #: 5  
County: GRAHAM Total Vertical Depth: 3940 feet

Operator License No.: 33764  
Op Name: INVESTMENT EQUIPMENT LLC  
Address: 17509 COUNTY ROAD 14  
FT. MORGAN, CO 80701

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3940	0	150 SX
SURF	8.625	198	0	150 SX

# 128.05

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2007 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BOB ALLEN Company: INVESTMENT EQUIPMENT LLC Phone: (405) 760-3682

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid level 500'.  
Bridge at 780' and 1690' - cleaned out to 1910' - bad casing.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/08/2007 1:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1900'. Allied pumped 50 sxs neat cement.  
Pulled to 1593'. Allied pumped 110 sxs cement with 200# hulls - circulated cement.  
PTOH. Squeezed 4 1/2" with 50 sxs cement.  
Max. P.S.I. 650#. S.I.P. 200#.  
Hooked up to backside. Allied pumped 25 sxs cement with 100# hulls.  
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3737	3898		

**INVOICED**  
DATE 3-16-07  
INV. NO. 2007061474

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Richard Williams*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 13 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

MAR 12 2007

PKT

DANE G. HANSEN TRUST #5 RICE  
 LOGAN, KANSAS  
 Contr. C-G DRILLING COMPANY Cty. GRAHAM  
 Geol. DICK NIXON Pool LAW

35-9-23W  
 NE NE NW

E. 2416 KB Cm. 1/28/69 Cp. 3/20/69 IP CO PMP EST 50  
 BOPD/KC 3737-3898  
 API 15-065-20,202

LOG Tops	Depth	Datum	Csg.
			8-5/8" 198/150 SX
			4 1/2" 3939/150 SX
ANH	1996	+ 420	DST 3720-43/1', WB, 85' SOCMW,
TOP	3449	-1033	BHP 108-91#, FP NA
HEEB	3667	-1251	DST 3775-93/1', WB, 90' OCM, BHP
TOR	3691	-1275	127-114#, FP NA
KC	3702	-1286	DST 3815-47/1', 20'M, BHP 597-
BKC	3930	-1514	208#, FP 18-36#
TD	3940	-1524	DST 3878-3903/75", 30'M, O/S,
			BHP 136-57#, FP 18-36#
			PF /3895-98, /3875-79, 3860-63,
			/3838-42, /3782-87, /3876-78,
			/3744-47, /3737-41, A 3000 (4
			BTM ZN) A 4000, NO TST, POP
			NO CORES

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS