

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03443-00-00  
Spot: SESENE Sec/Twnshp/Rge: 35-9S-20W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: WILSON C Well #: 8  
County: ROOKS Total Vertical Depth: 3778 feet

Operator License No.: 31783  
Op Name: MID-CONTINENT ENERGY OPERATING  
Address: 100 W. 5TH STREET, STE 450  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3789	0	w/unknown sxs cmt
SURF	8.625	220	0	w/unknown sxs cmt

**\$122.78**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2007 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: IRVIN HASELHORST Company: MID-CONTINENT ENERGY OPERATING Phone: (785) 625-4220

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Squeeze jobs: 750'-900' w/200 sxs; 1170'-1220' w/150 sxs.  
Unable to repair - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2007 11:30 AM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Ran tubing to 2500'. Allied pumped 160 sxs 60/40 pozmix - 10% gel with 500# hulls - circulated cement.  
PTOH. Allied squeezed 60 sxs cement with 100# hulls.  
Max. P.S.I. 1000#. S.I.P. 1000#.  
Hooked up to 8 5/8" - Allied pumped 100 sxs.  
Max. P.S.I. 150#. S.I.P. 150#.

**Perfs:**

Top	Bot	Thru	Comments
3775	3778	OH	

**INVOICED**

DATE 3-16-07  
INV. NO. 2007061477

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3

MAR 13 2007

CONSERVATION DIVISION  
WICHITA, KS

MAR 12 2007

PKT

FRANCIS OIL & GAS

#8 WILSON 'C'

35-9-20W  
SE SE NE

Contr. \_\_\_\_\_ ROOKS County

E 2255 R.B. Comm. \_\_\_\_\_ Comp. 4-22-55 IP 3000 BOPD

DRAW DOWN

Tops	Depth	Datum
HEEB	3459	-1204
LANS	3500	-1245
CONG	3745	-1490
ARB	3788	-1533
TD	3798	-1543

Casing  
 8" 220  
 5" 3789  
 DST 3524-64/1 HR, 90' H OCM  
 DST 3576-91/1 HR, 1330' OIL,  
 540' SLT WTR  
 DST 3640-85/1 HR, 295' OCM,  
 100' OIL  
 CO 3798: 1200' OIH

MARCOTTE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS