

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22866-00-00
Spot: CNESENE Sec/Twnshp/Rge: 31-9S-18W
3630 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: PYWELL Well Number: 1
County: ROOKS Total Vertical Depth: 3735 feet

Operator License No.: 8133
Op Name: HAMMERSCHMIDT, WILLIAM E
Address: 904 S SECTION LINE
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: 8/21.39
Surface Casing: Size 8.625 feet: 227 w/135 sxs cmt
Production: Size 4.5 feet: 3734 w/125 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/20/2001 1:00 PM

Plug Co. License No.: 8133 Plug Co. Name: HAMMERSCHMIDT, WILLIAM E

Proposal Rcvd. from: BILL HAMMERSCHMIDT Company: HAMMERSCHMIDT, WILLIAM E Phone: (785) 434-2403

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix -10% gel - 500# hulls.
Port collar at 1622' w/400 sxs 50/50 pozmix - 6% gel (05-09-1986).
WLM: 12-18-2001 - Fluid Level 260' - PBTB 3479'.
Perfs 3385' - 3428'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/20/2001 4:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2 3/8" tubing to 1650'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 200# hulls.
Pulled tubing to 1433'.
Allied pumped 50 sxs with 300# hulls - cement circulated.
PTOH. Allied squeezed with 35 sxs.
Max. P.S.I. 500#. S.I.P. 400#.
Hooked up to backside. Instant pressure 500#. Alt.II 400 sxs.

Remarks: ALLIED CEMENTING COMPANY - RUSSELL, KANSAS 67665

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

1/2/02
JAN 02 2002

KCC WICHITA

INVOICED

Form CP-2/3

DATE 01-03-02

INV. NO. 2002061166

DEC 31 2001

R.P. NIXON
 207 W. 12TH ST.
 HAYS, KS. 67601

#1 PYWELL


31-9-18W
 NE SE NE

CONTR JAY-LAN CORPORATION CTY ROOKS

GEOL _____ FIELD PYWELL

ELV 2181 KB SPD 2/26/86 CARD ISSUED 5/15/86 IP P 18 BO & 14 BWP

DRLG COMP 3/4/86 LKC 3385-3428
 SIMP 3687-3705 OA



LOG	Tops	Depth/Datum	API 15-163-22,866
SC	1602+	579	8 5/8 " 227, 4 1/2 " 3734
B/SC	1608+	573	NO CORES OR DST'S
HEEB	3344-	1163	MICT - CO, PF (LANS) 3385-3428, W / 2 SPF, AC 1500 GAL,
TOR	3368-	1187	GSO, PF (SIMP) 3687-3705, 3385, 3428, 3687-3690 & 3703-
LANS	3384-	1203	3705, AC 500 GAL, GSO, POP, P 18 BO & 14 BWP, COMMING-
BKC	3606-	1425	LED, 4/8/86
PENN/CONG	3627-	1446	
SIMP DOL	3686-	1505	
ARB	3720-	1539	
RTD	3735-	1554	