

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01916-00-01
Spot: SENESW Sec/Twnshp/Rge: 11-10S-19W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: HUSTED B Well #: 2
County: ROOKS Total Vertical Depth: 1575 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY - SUITE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	200		

\$51.19

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/07/2007 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING COM Phone: (785) 625-1118

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 700# hulls.
Washed down to 1575' - unable to get below - decided to P/A.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/07/2007 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 602' - hooked up Allied - washed out bridge - went to 1549'.
Allied pumped 75 sxs w/200# hulls - lost circulation.
Pulled tubing to 1013'.
Allied pumped 100 sxs w/200 # hulls - lost circulation again.
Pulled to 835'. Allied pumped 130 sxs w/300# hulls - circulated cement.
PTOH. Topped off w/20 sxs - 8 5/8" full.

Perfs:

INVOICED
DATE 3-16-07
INV. NO. 2007061474

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed Richard Williams
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 13 2007
Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS

MAR 12 2007

PKT