

To: **6 040999**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

X 12-30 15-163-01585-00-01
API NUMBER 15- E 16,521

NE NW SW, SEC. 30, T. 9, S, R 18 W/W
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT
8133
Operator License # _____
Operator: William E. Hammerschmidt
Name & Address _____
904 S. Sec Line
plainville, Ks. 67663

Lease Name Sellenberger Well # 3
County _____ Rooks 118.14
Well Total Depth 3635 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 191' w/cement

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____
Address Russell, Ks.

Company to plug at: Hour: 9:00 Day: 30 Month: Dec Year: 19 88

Plugging proposal received from Bill Hammerschmidt

(company name) Same as above (phone) _____

were: 5 1/2" casing set at 3612' w/100 sks. O.H. at 3612' - 35'. Base Dakota at 987';
Sq at 950' - 1150' w/250 sks (1956). Ordered 250 sks 65/35 Poz 10% Gel w/1/4 F.C. plus
plus 6 sks Hulls. (Plus 50 sks common)

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 30 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Pumped 50 sks common w/1/4# F.C. plus pumped in 5 1/2" casing
175 sks cement w/1/4# F.C. Max 800# S.I. 500# psi. Pumped in 8 5/8" casing 75 sks cement
w/1/4# F.C. plus Hulls mixed in cement. Max 800# S.I. 500# psi.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED
DATE 1-19-89
INV. NO. 23702

D.L.S.

Dennis Hamel