

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-01577-00-00

SW-SW-NE Sec. 30, T 9 S, R 18

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name HILGERS Well # 1

Operator: LADD PETROLEUM CORP.
Name & Address: BOX 520
GREAT BEND, KANSAS
67530

County ROOKS

Well Total Depth 3621 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 154'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address 1100 EAST 8th ST. HAYS, KANSAS.

Company to plug at: Hour: 1:00 AM Day: 25th Month: MAY Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO PHIL EMIG

(company name) LADD PETROLEUM CORP. (phone) 216-792-3571

were: 8 5/8" - 154' OUL w/? N.A. 5 1/2" SET @ 3621' w/? N.A.

No plug back. TOP OF PERFS. 3280' SQUEEZED TWICE @ 450' w/? N.A.

NO PIPE RECOVERY.

ORDER 250' 50% Pozmix 6% GEL-3% CA-CL, 15' GEL, 5' HULL'S, AND 8 5/8" PLUG.
PUMP IN ANNULUS AND IN 5 1/2" CSG. WITH PUMP TRUCK.

Signed *Marilyn Schmidt*
(TECHNICIAN) (201C)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 PM Day: 25th Month: MAY Year: 1983

ACTUAL PLUGGING REPORT ORDERED 250' 50% Pozmix 6% GEL-3% CA-CL.

15' GEL, 5' HULL'S, AND 5 1/2" PLUG. PUMPED IN WITH PUMP TRUCK.

PUMPED 85' IN ANNULUS, MAX. PRESSURE 150 PSI, PUMPED IN

5 1/2" CSG., 10' CMT., 3' HULL'S IN 40' CMT., 10' GEL, 25' CMT.,

5' GEL, RELEASE PLUG AND 90' CMT. - 5 1/2" ON VACUUM. ORDERED

ANOTHER 200' 50% Pozmix 6% GEL-3% CA-CL, 4' HULL'S (2) 25' FLO-SEAL.

Remarks: PUMPED IN AN ADDITIONAL 160' CMT IN 5 1/2" CSG, MAX PRESSURE, 600 PSI

ALSO PUMPED IN AN ADDITIONAL 40' CMT IN ANNULUS, MAX PRESSURE, 400 PSI

CEMENTED BY HALLIBURTON CMT.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed *Marilyn Schmidt*
(TECHNICIAN) (201C)

INVOICED

DATE 6-3-83
INV. NO. 4493-W

RECEIVED
STATE CORPORATION COMMISSION

5/27/83
MAY 27 1983

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82