



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C&G Drlg & Hansen Trust

Complete Address: 1107 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Thyfault Well No. 3

Location: NW SE NW Sec. 8 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3713 Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Messing  
Conservation Division Agent