

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
JAN 28 1967  
1-23-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lahr of B & B Drilling Inc. has this  
date requested permission to plug the following described well:

Mr. Lahr guarantees payment of the plugging fee.

Operator's full Name: Robinowitz Oil Company

Complete Address: 1322 East 50th Street Tulsa, Okla.

Lease Name: Rempe Well No. 5

Location: SW NE SE Sec. 21 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3580' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Lahr was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, set cementing plug at 550' and displace  
25 sc cement thru drill pipe. Heavy mud to 190' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Massey  
Conservation Division Agent