

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Vern Lang of Ranger Drilling Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Lebsack Oil Production, Inc.

Complete Address: P.O. Box 489 Hays, Ks. 67601

Lease Name: Allphn Well No. 1

Location: SE NE NE Sec. 32 Twp. 9 Rge. 19 (E) (W)

County: Rooks Total Depth: 3780'

Abandoned Oil Well Gas Well Input Well SWD Well D&A xxx

Other well as hereafter indicated: _____

Mr. Vern Lang was instructed to plug the well as follows:

8 5/8" 265' S.P. cuc. W/ 150 sacks common 2% Gel-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel- 3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 1020' W/ 70 sacks cement

2nd plug @ 260' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' w/ 10 sacks cement.

Circulate 10 sacks cement in rat hole.

Very truly yours,

Gilbert R. [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1982
CONSERVATION DIVISION
Wichita, Kansas