

State of Kansas



GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1959
CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 7-10-59, 19 , authorized the following plugging operation:

Operator's Full Name: Petroleum Inc

Complete Address: 352 N Broadway Wichita, Kans

Lease Name: Webster Well No. D-1

Location: SW NW SE Sec. 34 Twp. 9 Rge. 19 (E) (W)

County: Rooks Total Depth: 3711

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Circulate hole with heavy mud, set cementing plug at 540' with 20 sax cement, heavy mud to 180', set plug and 20 sax cement, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar

Very truly yours,

Signed: [Signature]
Conservation Division Agent