

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 22 1963  
 10-22-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Knight of Knight Casing Pulling has this

date requested permission to plug the following described well:

Mr. Bud Ainsworth guarantees payment of the plugging fee.

Operator's full Name: A (Bud) Ainsworth

Complete Address: 715 4th Natl Bk Wichita, Kans

Lease Name: O'Brien Well No. 1

Location: SW NW NE Sec. 34 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3550 Oil Well       

Gas Well        Input Well        SWD Well        D & A        Lost Hole wash down

Mr. Knight was instructed to plug the well as follows:

Plug off bottom with sand- set 3 sax cement with dump bailer at 3400'  
stop 4 1/2" at 600' circulate hole with heavy gel mud at 600' - displace  
20 sax cement through 4 1/2" at 600' - heavy mud to 250' - displace 20 sax  
cement through 4 1/2" at 250', heavy mud to 35', set bridge and fill with  
cement to bottom cellar.

Very truly yours,

Eldon Peely  
 Conservation Division Agent