

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

15-163-20774-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3/22/78  
MAR 22 1978  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Myers of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Myers guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg.

Complete Address: 617 Union Center, Wichita, Kansas

Lease Name: Dauphin-DesMarteau Well No. 2-3

Location: 1200'FWL & 330'FSL SW Sec. 7 Twp. 9 Rge. (E)(W) 20

County: Rooks Total Depth 3872' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Myers was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 750' thru drill

pipe. Heavy mud to 150' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent