

15-163-01582-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Oil Property Management, Inc.

Complete Address 300 Insurance Bldg., Wichita, Kansas 67202

Lease Name Jelinek Well No. 4

Location NE SE NE Sec. 30 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3660'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Allied Cementing

Address Russell, Kansas License No.

Operation Completed: Hour 11:30 A Day 30 Month 12 Year 1970

The above well was plugged as follows:

Total Depth 3660' 8 5/8 csg set at 158' cwc 110 sk.

5 1/2 csg set at 3659' cw 100 sk cmt.

5 1/2 csg PBTB 3630' and perf. (3402-3430)

5 1/2 csg squeezed thru Dakato Section. No pipe recovered.

Pumped down annulus (5 1/2-8 5/8) with 60 sk cmt. Pres. 200 lbs.

Pumped down 5 1/2 csg with 30 sk cmt - 30 sk gel W/5 sk hulls - release plug and pumped

70 sk cmt. Max pres. 800 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 1-5-71
INV. NO. 3149-W