

15-163-20289-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leben Drilling, Inc.

Complete Address P. O. Box 486 Great Bend, Kansas 67530

Lease Name Cerrow Well No. 1

Location NW NW SE Sec. 5 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3500'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pilling, Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 5 P Day 8 Month 12 Year 1970

The above well was plugged as follows:

Total Depth 3500' 8 5/8 csg set at 210' cwc 165 sk.

5 1/2 csg set at 3489' cw 150 sk cmt.

5 1/2 csg PBTD 3470' with top perf. (3366)

Set wood plug at 3300' -poured 10' sd and dumped 5 sk cmt W/dump bailer. (3300-3250)

Cutoff and recovered 2800' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls - 70 sk poz 6% - 8 sk gel -

released plug and pumped 50 sk poz 6%. pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Messing  
Well Plugging Supervisor

DATE 12/9/70

INV. NO. 3025-W