

15-163-20292-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
2/17/70  
FEB 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leben, Et al

Complete Address 200 Sutton Place Wichita, Kansas

Lease Name Hayden Well No. 3

Location SE NE NW Sec. 5 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3528'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 9:30A Day 16 Month 2 Year 1970

The above well was plugged as follows:

RTD 3528' 8 5/8 csg set at 210' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt  
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 2/17/70  
INV. NO. 1444-0