

15-163-00734-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

*af* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tomlinson Oil Co., Inc.

Complete Address 1125 Wichita Plaza, Wichita, Kansas

Lease Name Barber Well No. 1

Location NE NE NE Sec. 31 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3740'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour        Day 16 Month 5 Year 1970

The above well was plugged as follows:

Total Depth 3740' 8 5/8 csg set at 186' cwc

5 1/2 csg set at 3719' cw 100 sk cmt.

5 1/2 csg PBTB 3700 and perf. (3372 - 3375)

Set 5 1/2 wood plug at 3300' poured sd (3275-3300) 5 sk cmt (3235-3275)

Shutoff and recovered 815' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls -- 50 sk poz 6% --

5 sk gel -- plug and 50 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 5/22/70  
INV. NO. 1905-4