

15-163-20768-00-00

Form CP-3
Rev. 6-4-68

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1/27/78
JAN 27 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,768

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Earl Thomason

Complete Address 2914 Hillcrest Dr., Hays, Kansas

Lease Name Sollenberger Well No. 4

Location NW NE SW Sec. 30 Twp. 8 Rge. 9 (E) (W) 18W

County Rooks Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.

Operation Completed: Hour 11 A Day 26 Month 1 Year 1978

The above well was plugged as follows:

RTD 3630' 8 5/8 csg set 175' cwc 125 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bee Massey
Well Plugging Supervisor

DATE 1-30-78

INV. NO. 6662-W