



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6/10/75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Myrlin Monroe

Complete Address 512 South Wyoming, Plainville, Kansas 67663

Lease Name Mayhew Well No. 2

Location SE SW NW Sec. 31 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3718' ^{KCC} 3720' ^{ZAP}

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 9:30 A Day 5 Month 6 Year 1975

The above well was plugged as follows:

RTD 3718' 8 5/8 csg set 214' cwc 150 sk.

5 1/2 csg set 3714' cw 100 sk cem. Top perf, (3169')

Set 5 1/2 wood plug at 3150' -poured 25' sd. -dumped 5 sk cmt W/dump bailer. (3150-3090)

Cutoff & recovered 1200' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg : 18 sk gel & water W/300 lbs hulls -70 sk 50-50 poz

6% -10 sk gel & water -released plug & 50 sk 50-50 poz 6% by Allied Cem. Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/13/75

INV. NO. 1472-W