

15-163-00776-00-00

Form GP-3
Rev. 6-26-62

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
10/25/63
OCT 25 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clark T. Snider
Complete Address: 526 Union Center Wichita, Kans
Lease Name Baumgartner Well No. B-1
Location NW NE SW Sec. 31 Twp. 9 Rge. (E) (W) 18
County Rooks Total Depth 3730
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Southwest Casing Pulling
Address: Great Bend, Kans License No. 399
Operation Completed: Hour 10AM Day 25 24 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" 210' circulated with cement - 5 1/2" 3725' with 100 sax cement -
Plugged back with cement to 3620'.

Pulled 3090' 5 1/2" to 525' - pumped mud through 5 1/2" at 525' - hole pressured
up - unable to circulate - pulled pipe to 357' - tried to circulate with
mud - hole pressured up - pulled pipe to 300' and finished circulating
hole with mud, used 22 sax gel - displaced 40 sax cement through 5 1/2" at
300' - heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Peety*
Well Plugging Supervisor

DATE 10/28/63
INV. NO. 7961-11