

15-163-02684-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO.

LOCATION

SE SW 1/4 E 1/4 Sec 28  
SW SE NE *28*

SEC. 28 TWP. 9 RGE. 18

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 5 Lease Rempe

Operator Skelly Oil Co Address Hutchinson, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3675 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1500' circulated with 600 sax cement.

Circulated hole with heavy mud, pumped in 25 sax cement

at 3675', mud to 300', set cementing plug and 25 sax cement

at 300', mud to 65', set cementing plug and 25 sax cement to

bottom cellar - all cement displaced through drillpipe by

Halliburton Co.

RECEIVED  
STATE CORPORATION COMMISSION  
6/4/52  
JUN 4 - 1952

PLUGGING  
FILE SEC 28 T 9 R 20  
BOOK PAGE 20 LINE 27

CONSERVATION DIVISION  
Wichita, Kansas

Edmond T. Kelly  
District Conservation Agent

Date 5-31-52